


## 1<sup>ST</sup> STARTING OF C.H. BOILER FUWI

1. Removing two screws from 8- modular switchgear.
2. Checking correctness connections - AC power, supply of feeder, sensors: temperature feeder, boiler temperature, ZTK.
3. Checking correctness connections - cable 7 wires - wires: PE, 1,2 - blower, 3,4 - photodiode, 5,6 - lighter.
4. Removing sensors, power pumps, hot water and / or CO (3-core cable), power four-way or three-way valve on the side bar.
5. Top rail controller:
  - Connection of hot water sensor (T<sub>cwu</sub> – pin 2,3)
  - Connection of central heating (T<sub>co</sub> – pin 8,9)
  - Connection of return sensor (T<sub>pow</sub> – pin 10,11)

Sensors T<sub>co</sub> i T<sub>pow</sub> CONNECT WHEN IS USED THREE-WAY FOUR AND FOUR-WAY VALVE.

6. Connect with 3-core cable of Co and CWU pumps ( ex ample connection pump for below controller)
  - Pin 3 – hor water pump
  - Pin 4 – central heating pump



7. Connect 3-way Or 4-way valve (lower bar controller - pin 1,2)

M0 – Valve closing

M1 – Valve opening

8. Place the sensor on the installation:
  - T<sub>cwu</sub> – on hot water heater
  - T<sub>co</sub> – on output boiler
  - T<sub>pow</sub> - on return of boiler
9. Check the correct connections and start the c.h. boiler.
10. On Menu -> Measurements check, when temperature is displayed. If instead the temperature is ERR, although sensors are connected, that is mean that, this is incorrect connection of sensors.
11. We are setting every c.h. boiler parameters: c.h. boiler temperature, hot water temperature, minima pump temperature, feeding and bower.

BOILER POWER [KW]	9	15	22	30	44	55	80	100
BURNER POWER N O 2 (100%) FEEDING [S]	5	7	10	16	22	12	20	24
BURNER POWER N O 1 FEEDING [S]	From 30% up to 100% of feeding time of burner power No 2							

12. Star the boiler and make first fire up the boiler.
13. At the first pre-spammed, check (shine a flashlight) if Filling is too much fuel (is unloaded), reduce the initial charge in the service mode.
14. Check the the proper operation of all equipment and automation in the "test outputs" (investigation to setting temperature, switching up and and removable pumps and 3-way and 4-way valves).

